


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 17 Twp. 20S Rge. 12W (A) (W)
Location as "NE/CNWxSWx" or footage from lines. NE-NE-NE
Lease Owner Petroleum, Inc.
Lease Name Christiansen "B" Well No. 1
Office Address Route #2, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 11 19 59
Application for plugging filed May 11 19 59
Application for plugging approved May 11 19 59
Plugging commenced May 11 19 59
Plugging completed May 11 19 59
Reason for abandonment of well or producing formation No producible zone

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3496 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 253' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud up with heavy mud to 245', followed by wooded plug, and 1/4 sack hulls, Placed 25 sacks cement through drill pipe to top of plug. Mud up to 40' followed by wooden plug and 1/4 sack hulls, filled hole to base of well celler with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1959

CONSERVATION DIVISION
Wichita, Kansas

5-28-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address Route #2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Don Searle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
Route #2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 19 59

Arthur J. Wiles
Notary Public.

My commission expires April 14, 1963

PLUGGING
FILE SEC. 12 T. 20 R. 12 W
BOOK PAGE 38 LINE 4

WELL LOG

15.009. 05215. 0000

COMPANY PETROLEUM, INCORPORATED

SEC. 17 T. 20S R. 12W

FARM CHRISTIANSEN "B" No. 1

LOC. NE, NE, NE


TOTAL DEPTH 3496'

COUNTY BARTON CO., KANSAS

COMM. May 4, 1959

COMP. May 11, 1959

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 253' W/225 sax.

ELEVATION 1837' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|------|----------------------|
| 185 | Sand, clay & gravel |
| 195 | Shale |
| 500 | Shale & shells |
| 638 | Shale |
| 677 | Anhydrite |
| 1480 | Shale |
| 1600 | Shale & lime streaks |
| 1935 | Lime |
| 2056 | Lime & shale |
| 2410 | Lime, shale & shells |
| 2720 | Shale & shells |
| 2915 | Shale & lime streaks |
| 3050 | Lime |
| 3240 | Lime & shale |
| 3445 | Lime |
| 3496 | Cherty conglomerate |
| 3496 | T. D. |

RECEIVED
MAY 28 1959
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss:

PLUGGING
FILE SEC. 12 T. 20 R. 12W
BOOK PAGE 38 LINE 4

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 CHRISTIANSEN "B" well

Subscribed and sworn to before me this 26th day of May 19 59

My Commission Expires: April 14, 1963

Verne A. Morris
Arthur J. Wiles
NOTARY PUBLIC