


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 17 Twp. 20S Rge. (E)12 (W)
Location as "NE/CNW/SE/SW" or footage from lines C NE SE NW
Lease Owner HERMAN GEO. KAISER, Oil Producer
Lease Name Welsh "B" Well No. 1
Office Address 909 Palace Bldg., Tulsa, Oklahoma 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 23 19 68
Application for plugging filed Verbal Authority 19
Application for plugging approved Verbal Authority 19
Plugging commenced August 23 19 68
Plugging completed August 23 19 68
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	264'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,458 feet (rotary total depth) to 250 feet. Set bottom plug at 250 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1968
CONSERVATION DIVISION
Wichita, Kansas
8-29-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, INC.
Address 200 N. Main St., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B Romer
200 N. Main St., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 19 68

My commission expires April 21, 1971
Martha Hartpence
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY 15.009.20261.0000
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 509 EAST MURDOCK - WICHITA, KANSAS

COMPANY Herman Geo. Kaiser, Oil Producer

SEC. 17 T. 20S R. 12W

FARM Welsh "B"

NO. 1

LOC. C NE SE NW

TOTAL DEPTH 3,458'

COUNTY Barton

COMM. August 16, 1968


COMP. August 23, 1968

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, INC.

ISSUED



CASING

20	10	
15	8 - 5/8"	264' cemented with 250 sx cement
12	6	
13	5	

PRODUCTION 1858 KB

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	137
Pyrite	142
Sand, Shale & Pyrite Streaks	264
Red Bed & Shale	665
Anhydrite	693
Shale	810
Shale & Shells	1510
Shale & Lime	1815
Lime	1990
Shale & Lime	2550
Shale with Lime Streaks	2755
Lime & Shale	2965
Lime	3035
Lime & Shale	3230
Lime	3425
Lime & Conglomerate	3458
Rotary Total Depth	3458

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 29 1968
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 27th day of August, 1968.

Martha Hartpence
 Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971