


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 17 Twp. 20S Rge. (E)12 (W)

Location as "NE/CNW/SW" or footage from lines C SE SW NE

Lease Owner H-30, INC.

Lease Name Schartz Well No. 2

Office Address 200 N. Main, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 13, 1969 19

Application for plugging filed Verbal Approval 19

Application for plugging approved Verbal Approval 19

Plugging commenced April 13, 1969

Plugging completed April 13, 1969

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,505 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		RECEIVED		10-3/4"	270	None
		STATE CORPORATION COMMISSION				
		APR 23 1969	4-23-1969			
		CONSERVATION DIVISION				
		Wichita, Kansas				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,505 feet (total rotary depth) to 400 feet. Set bottom plug at 400 feet and cemented with 60 sacks cement. Filled hole with heavy rotary mud to 260 feet. Set plug at 260 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 1/2 sack hulls and 15 sacks cement, 2 sacks cement in rathole. Plugged through drill pipe with Halliburton Pump Truck.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, INC.

Address 200 N. Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Merle Britting

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting

200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 1969

My commission expires April 21, 1971

Martha Hartpence
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY H-30, INC.

SEC. 17 T. 20S R. 12W
LOC. C SE SW NE

FARM Schartz

NO. 2

TOTAL DEPTH 3,505

COUNTY Barton

CDMM.


COMP. April 13, 1969

KANSAS

BHDY OR TREATED

CONTRACTOR H-30, INC.

ISSUED



CASING

20 10-3/4" 270' cemented with 300 sacks cement.

15

8

ELEVATION 1847 KB

12

6

13

5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay and sand	200
Shale	270
Shale and red bed	600
Anhydrite	675
Shale	1565
Lime and Shale	1980
Shale and shells	2195
Shale	2495
Shale and lime streaks	2630
Shale	2715
Shale and lime	2895
Lime with shale streaks	2995
Lime and shale	3165
Lime	3505
Rotary total depth	3505

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1969
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log the above described well as shown by the drilling reports.

H-30, INC.

Merle Britting
Merle Britting

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 22nd day of April, 1969.

Martha Hartpence
Martha Hartpence-Notary Public

My Commission Expires:

April 21, 1971