

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Ritting Building
Wichita, Kansas

Barton

County. Sec. 26 Twp. 20 Rge. 12 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE SE
Lease Owner B - H - P
Lease Name GALLIART Well No. # 3
Office Address Box 62, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed June 3, 19 49
Application for plugging filed June 4, 19 51
Application for plugging approved June 2, 19 51
Plugging commenced May 18, 19 51
Plugging completed May 27, 19 51
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 207, Great Bend, Kansas
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3423' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	240'	Cemented
				5 1/2"	3404'	2704'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3423' feet to ----- feet for each plug set.

Filled hole from 3423' to 3385' with sand
Dumped 5 sacks cement from 3385' to 3350'
Mudded hole from 3350' to 240'
Set 10' rock bridge from 240' to 230', Mudded from 230' to 25'
Dumped 10 sacks cement from 25' to cellar

6-29-1951

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B - H - P
Address Box 62, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leon F. Huff, Partner of


(Employer of above described well) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon F. Huff
Box 62, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of June 19 51

Reggy L. Shank
Notary Public.

My commission expires April 4, 1955



DRILLING LOG

OPERATOR: W. H. Black LOCATION: SWc SE SE
 FARM NAME: Galliart Section 26-20S-12W
 WELL NUMBER: 3 Barton County, Kansas

CONTRACTOR: W. H. Black CASING RECORD:
 8-5/8" @ 240'
 ROTARY COMMENCED: May 3, 1949 Cem. 225 sacks
 ROTARY COMPLETED: May 12, 1949 5-1/2" @ 3398'
 Cem. 125 sacks

ELEVATION: 1825 D. F. INITIAL POTENTIAL:

Figures denote bottom of formations

Sand and Shale 218
 Red Bed 590
 Anhydrite 620
 Red Bed, Shale and Shells 835
 Shale and Shells 1100
 Salt 1390
 Shale and Shells 1630
 Shale and Lime 2050
 Lime and Shale 2275
 Shale and Lime 2540
 Lime and Shale 3140
 Lime 3405

TOPS

Anhydrite 590
 Heebner 3002
 Kansas City 3143
 Simpson 3386
 Sand 3398

Total Rotary Depth
 Gable Tool Total Depth 3416

STATE OF KANSAS)
) SS
 SEDGWICK COUNTY)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN - 7 1951
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that the foregoing is, to the best of my knowledge and belief, a full, true and correct drilling log as shown by the daily drilling reports in connection with the aforesaid well.

Leon F. Huff
 Leon F. Huff,
 Attorney-in-Fact for W. H. Black

Subscribed and sworn to before me, the undersigned, a Notary Public, this 16th day of June, 1949.

PLUGGING
 FILE SEC-26-20S-12W
 ROCK FACE 85 LINE 33

Mildred Hobbes
 Notary Public

My commission expires November 5, 1951.