

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County, Sec. 26 Twp. 20S Rge. 12 (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Lee Drilling Company

Lease Name Bryant "C" Well No. 1

Office Address Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 5-9-49 19

Application for plugging filed 1-30-51 19

Application for plugging approved 1-30-51 19

Plugging commenced 2-4-52 19

Plugging completed 2-10-52 19

Reason for abandonment of well or producing formation Well stopped producing

If a producing well is abandoned, date of last production 3-1-51 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Arbuckle line Depth to top 3382 Bottom 3425 Total Depth of Well 3425 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"		2658'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 3425' to 3366'. Checked sand to 3334' and ran 5 sacks of cement. Halliburton Oil Well Cementing Company pumped in 50 sacks of mud and 75 sacks of cement which filled to top. Plugging completed.

STAMP: FEB 29 1952
2-29-1952

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Henry C. Thompson (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God,

(Signature) Henry C Thompson

510 Philtswar Bldg., Tulsa, Oklahoma

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of February, 1952

Margaret B. Mueller
Notary Public.

My commission expires December 5, 1955

25-8390-5
PLUGGING
FILE SEC 26T 20 R 12W
BOOK PAGE 141 LINE 44

15.009 .15615.0000

Well Log

ALPINE OIL & ROYALTY CO., INC.	Elevation:	1824 RB
Contractor: Quaker Drilling Co., Inc.	Commenced:	2-26-49
Bryant C-1	Completed:	5-9-49
NW NW SW Sec. 26-20S-12W	Production:	32 barrels
Barton Co., Ks.		

Casing Record:
 Set 8 5/8" 260' cemented with 225 sacks

(Figures indicate bottom of Formations)

<u>FORMATION:</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Clay and Sand	80	Heebner	2997 -1173
Sand	185	Brown Lime	3126 -1302
Shale	260	Lansing	3137 -1313
Shale & Red Bed	613	Arbuckle	3369 -1545
Anhydrite Lime	640		
Shale & Lime	900	Set 5 1/2"	3370 -1546
Shale, Shells & Salt	1415	T. D. (r)	3372 -1548
Lime	1570		
Sandy Lime	1705		
Lime & Shale	2145		
Shale & Shells	2320		
Shale & Lime	3369		
Arbuckle	3372 TD		

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the NW NW SW of Section 26, Township 20 South, Range 12 West, Barton County, Kansas.

ALPINE OIL & ROYALTY CO., INC.

By: _____

Subscribed and sworn to before me this -- day of _____, 1949.

 Notary Public

My Commission Expires:

