

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.009.15619.0000

LEASE NAME Marchand

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line
SW/NE/NW 990' FNL-1650' FWL

SEC. 26 TWP. 20S RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 1-25-93

Plugging Completed 2-1-93

LEASE OPERATOR MIDWAY DRILLING, INC.

ADDRESS P.O. Box 1325 Great Bend, Kansas 67530

PHONE# 316, 793-7412 OPERATORS LICENSE NO. 5568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Don Butcher (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3479'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10"	260'	None
				5-1/2"	3356'	1278'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3200' and 5 sacks cement. Shot pipe @ 2400', 2200', pipe parted @ 1278'. Pumped 165 sacks cement down 5-1/2" casing, pulled up to 750', pumped 200 sacks, pulled up to 250', pumped 35 sacks, circulated cement to surface and pulled rest of pipe. 65/35 Pos. 8% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Midway Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 4th day of February

Irene Herzig
Notary Public

My Commission Expires:

