

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009-15592.0000 (of this well)

Operator's Full Name Icer Addis
Complete Address Drawer 8038 Wichita, Kansas 67208
Lease Name Pete Scheufler Well No. 2
Location C NW/4 Sec. 24 Twp. 20 Rge. 12 (E) X (W) X
County Barton Total Depth 3349'
Abandoned Oil Well X Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated This well was used as A SWD when quit producing.
Plugging Contractor Glenns Casing Pulling, Inc.
Address Box 413 Ellinwood, Kansas 67526 License No. 832
Operation Completed: Hour 3:00 PM Day 31 Month 8 Year 1979

The above well was plugged as follows:

Sanded back to 3270' and 6 sx cement with dump bailer.

Squeezed thru 10 3/4" surface casing with 3 sx hulls,

10 sx mud gel, 1 sx hulls, and 175 sx cement.

max pres. 700#. Shut in pres. 300#.

Recovered 548' of 6" casing.

3323' of 6" casing cemented with 250' sx cement

258' of 10 3/4" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

9-6-79

NO.

0355

Signed:

Ramon R. Rankins
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION

SEP - 4 1979

9-4-79
CONSERVATION DIVISION
Wichita, Kansas