



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_  
LOCATION SE 1/4 S 1/2 NW SE  
SEC. 26 TWP. 10 RGE. 12W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Schreisel Schrepel  
Operator Phillips Petro. Co Address Box #779 - G. Bend, Kansas  
Field \_\_\_\_\_ County Barton  
Total Depth 3452 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8 - 292 ft - Circulated with cement  
5 1/2 casing set at 3082 ft - Plugged back from bottom  
& 3128 ft with Lane Wells Plug & cement - Filled  
with Chat from 3128 ft to 3015 ft - Plugged 5 sacks of  
cement at 3015 ft - Shot & pulled the 5 1/2 casing -  
Filled with mud to 272 ft - Set rock bottom & 5 sacks  
of cement at 272 ft - Mud to 30 ft - Plugged  
Cement at the surface

OCT 21 1949  
STATE CORPORATION  
C. W. [Signature]  
District Conservation Agent

Date 10 - 19 - 49

**PLUGGING**  
FILE SEC 26 TWP 10 RGE 12W  
BOOK 100 LINE 35

F