

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06372-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 19-13S-14W
3022 feet from S Section Line, 4434 feet from E Section Line
Lease Name: GAYNOR Well #: 3
County: RUSSELL Total Vertical Depth: 3192 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3186		400 SX
SURF	8.625	134		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2018 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEVIN WILES Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2018 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

06/07/2018 - Rigged up and mudded up. Ran drill collar and tagged at 115'. Drilled down to 140' and lost circulation and drilling iron with no advancement in depth.
06/12/2018 - Swift Service rigged up and pumped down the casing with 50 sx cement followed by 50 sx cement w/50 # hulls mixed in. Shut down and WOC. Pumped 150 sx cement w/200 # hulls mixed in. Pressure started to climb to 300 #. Braden head blew out and circulated mud and cement out. Shut down after good cement was in cellar. Casing was full.

GPS: 38.90852 -098.92571

INVOICED
JUL 12 2018

Remarks: SWIFT SERVICES, INC. TICKET # 27328

Plugged through: CSG

District: 04

Signed Ray A Dinkel

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

JUN 19 2018