

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-30103-00-00
Spot: NENWSESW Sec/Twnshp/Rge: 7-17S-10W
999 feet from S Section Line, 3623 feet from E Section Line
Lease Name: ANDREA Well #: A-1
County: ELLSWORTH Total Vertical Depth: 3356 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3354		150 SX
SURF	8.625	673		500 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2018 10:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Revd. from: KEVIN WILES SR Company: AMERICAN WARRIOR INC. Phone: (620) 275-2963

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/24/2018 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPTED TO CLEAN OUT BOTTOM OF WELL-GOT SAND PUMP STUCK AT APPROX. 3034'. PERFORATED AT 1350', 1000' AND 725'. RUN TUBING TO 3030' AND PUMPED 50 SX'S COMMON WITH 3% CC. PULLED TUBING TO 1300' AND WAITED APPROX. 1 HOUR. TAGGED CEMENT AT 2710'. PUMPED 35 SX'S COMMON WITH 3% CC AT 1350', PULLED TUBING TO 1000' AND WAITED APPROX. 1 HOUR. TAGGED CEMENT AT 1225'. PUMPED 35 SX'S COMMON WITH 3% CC AT 1000', PULLED TUBING TO 725' AND CIRCUALTED 60-40 POZ, 4% GEL TO SURFACE. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3084	3252	CSG	

INVOICED
JUL 12 2018

Remarks: QUALITY CEMENT TICKET #6844. DENIED TA WELL.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)