

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20465-00-00
Spot: S2NWNW Sec/Twnshp/Rge: 9-33S-6E
3996 feet from S Section Line, 4684 feet from E Section Line
Lease Name: CHRISTENSON Well #: 2-C
County: COWLEY Total Vertical Depth: 3184 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3184		100 SX
SURF	8.625	197		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2018 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: _____ Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS / 40 SXS @ 3065', CIRCULATE & PERFORATE 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/14/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH WITH TUBING @ 3065', QES ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL, 2% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2710'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 350'-351' (4 HOLES). RIH WITH TUBING @ 370', QES ESTABLISHED CIRCULATION, MIXED & PUMPED 180 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE WITH 10 SXS. CEMENT TICKET #54534.

Top	Bot	Thru	Comments
3112	3134	CSG	

INVOICED
JUL 12 2018

Remarks: DENIED TA / 10 YEAR, LENGTH OF TIME / COMPLIANCE LIST

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

VJK