

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21369-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 20-20S-19W
1098 feet from S Section Line, 4282 feet from E Section Line
Lease Name: BARTONEK Well #: 20-13-1
County: PAWNEE Total Vertical Depth: 2460 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2458	0	WITH 125 SX CMT
SURF	8.625	495		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/14/2018 12:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: RUN TBG TO 2200' & SPOT 30 SX CMT & 250# HULLS. PULL TBG TO 1350' & SPOT 25 SX CMT. CIRCULATE CMT TO SURFACE FROM CASING LEAK AT 700' INSIDE & OUT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/15/2018 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

5/14/18: RAN TBG TO 2200' & MIXED 30 SX CMT & 100# HULLS. PULLED TBG TO 1350' & MIXED 25 SX CMT. PULLING TBG & THE 4 1/2" CASING CAME LOOSE FROM HEAD. SHUT DOWN. 5/15/18: REMOVED 6' SUB & WELD ON A NEW COLLAR. PRESSURED & HELD AT 500 PSI. PERFORATE AT 530' & CIRCULATE CMT TO SURFACE IN & OUT WITH 190 SX CMT.

INVOICED
JUL 12 2018

Perfs:

Top	Bot	Thru	Comments
2220	2289		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
MAY 22 2018
KCC DODGE CITY