

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-08443-00-02
Spot: N2NESW Sec/Twnshp/Rge: 28-15S-12W
2310 feet from S Section Line, 3300 feet from E Section Line
Lease Name: KLUSENER Well #: 2
County: RUSSELL Total Vertical Depth: 3279 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: PO BOX 329
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3273		50 SX
SURF	10	190		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2018 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE ROTH Company: BENNETT & SCHULTE OIL CO Phone: (785) 623-6543

Proposed Plugging Method: Ordered 75 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2018 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Well was dug up and verified 10 " casing at surface. Less than 2 seconds to bottom. Welder plumbed up to surface with 5 1/2" casing. Express Well Service rigged up a single drum, ran bit in and stacked out at 77'. Rigged up a double drum with mud pump and swivel. Ran a 4 7/8" bit into well and started to drill with no progress. Ran in 2 drill collars and drilled for 4 1/2 hours with very little progress. Circulated old cottonseed hulls, dry gel and very small cement chips. Stopped drilling since no progress was being made. Ran tubing down to 62' and pumped 45 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 15 sx cement with 300 psi. Well stayed full.
05/10/2018 - Visually checked well and it was full of cement.

GPS: 38.71788 -098.66443

INVOICED

JUL 12 2018

Remarks: QUALITY CEMENTING TICKET # 762

Plugged through: TBG

District: 04

Signed _____

Ray Dinkel

(TECHNICIAN)

CM

KCC WICHITA

MAY 31 2018

RECEIVED