

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-20091-00-00  
Spot: NENESE Sec/Twnshp/Rge: 31-16S-19W  
2323 feet from S Section Line, 333 feet from E Section Line  
Lease Name: LITTLER FRANK Well #: 2  
County: RUSH Total Vertical Depth: 3818 feet

Operator License No.: 5364 String Size Depth (ft) Pulled (ft) Comments  
Op Name: BEREN CORPORATION PROD 4.5 3809 0 WITH 200 SX CMT  
Address: 2020 N. BRAMBLEWOOD SURF 8.625 324 WITH 300 SX CMT  
WICHITA, KS 67206

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/04/2018 10:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Revd. from: MARK LEIKER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 60 SX CMT & 200# HULLS. RUN BOND LOG.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/04/2018 8:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

WELL WAS FLOWING AT THIS TIME FROM A CEDAR HILLS BREAK IN. RUN TBG TO 3750' & SPOT 60 SX CMT & 200# HULLS PULL TBG. THE WELL HAD BEEN SQUEEZED WITH 100 SX CMT AT 1140'. LOGGED WELL 1350' TO SURFACE. FOUND CMT 1200' TO 910'. PERFORATED CASING AT 1350'. RAN TBG TO 1350' & SPOTTED 40 SX CMT, 20 SX CMT WITH HULLS, 20 SX CMT WITHOUT HULLS. TRIED TO RUN CIBP IN CASING TO 750'. PLUG GOT STUCK AT 680'. COULDN'T PULL IT OUT SO SET PLUG AT 680'. STILL COULD NOT PULL REST OF TOOL OUT. PULLED UNTIL LINE PARTED. LEFT REST OF TOOL IN WELL AT 680'. PERFORATED AT 645' & PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE. SHUT IN WITH 900# PRESSURE.

Perfs:

Top	Bot	Thru	Comments
3809	3818		OH
3470	3475		CSG

INVOICED


JUL 12 2018

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
JUN - 5 2018  
KCC DODGE CITY

5A