

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-02908-00-00  
Spot: NESESW Sec/Twnshp/Rge: 17-9S-21W  
990 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: COOLEY AB LEASE Well #: A8  
County: GRAHAM Total Vertical Depth: 3797 feet

Operator License No.: 34318

String Size Depth (ft) Pulled (ft) Comments

Op Name: BEREXCO LLC

L1 4.5 3545

Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

PROD 5.5 3792

75 SX

SURF 8.625 163

100 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/17/2018 1:00 PM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: JEREMY HANKINS

Company: BEREXCO LLC

Phone: (913) 209-3846

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Pulled 2642' of 4 1/2" liner.  
CIBP set at 3721'.  
Perforations: 3793' - 3797', 3526' - 3682'.

Plugging Proposal Received By: MARVIN MILLS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 05/17/2018 2:30 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Shot perforations at 160', 1010', 1763' and 2350'. Ran tubing to 3384' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 2794' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1842' and pumped 170 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 85 sx cement. Shut in pressure 100 psi. Visually checked backside and found that cement fell approximately 100'. Topped off with dry cement.

Top	Bot	Thru	Comments
3793	3797		
3526	3682		

GPS: 39.26610 -099.69063

INVOICED


JUL 12 2018

Remarks: GLOBAL CEMENT TICKET # 3325

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

JUN 12 2018

CONSERVATION DIVISION  
WICHITA, KS

MAY 22 2018

Form CP-2/3