

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-20127-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 13-11S-23W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: CARPENTER LEASE Well #: 1  
County: TREGO Total Vertical Depth: 3725 feet

Operator License No.: 34318 String Size Depth (ft) Pulled (ft) Comments  
Op Name: BEREXCO LLC PROD 5.5 3725 175 SX  
Address: 2020 N. BRAMBLEWOOD SURF 8.625 229 150 SX  
WICHITA, KS 67206

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/12/2018 11:30 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 465 sx 60/40 pozmix 4% gel cement and 700 # hulls.  
Perforations: 3429' - 3432', 3484' - 3490', 3500' - 3502', 3540' - 3544', 3552' - 3556', 3570' - 3574', 3583' - 3588' and 3658' - 3662'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/12/2018 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Shot perforations at 220', 895', 1750' and 2350'.  
Ran tubing to 3644' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 3005' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2113' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1227' and pumped 120 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 25 sx cement. Tied on to backside and squeezed with 5 sx cement.

GPS: 39.08894 -099.82747

INVOICED

JUN 12 2018

Remarks: GLOBAL CEMENT TICKET # 3361

Plugged through: TBG

District: 04

Signed

Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 25 2018

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

JUN 18 2018