

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21086-00-00
Spot: NWSENWNE Sec/Twnshp/Rge: 22-11S-15W
4322 feet from S Section Line, 1735 feet from E Section Line
Lease Name: REICH D Well #: 2
County: RUSSELL Total Vertical Depth: 3495 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>3956</u>	PROD	4.5	3361		75 SX
Op Name: <u>BRUNGARDT OIL AND LEASING INC.</u>	SURF	8.625	242		160 SX
Address: <u>213 W. 7TH STREET PO BOX 871</u> <u>RUSSELL, KS 67665</u>					

Well Type: SWD UIC Docket No: D19161.0 Date/Time to Plug: 04/27/2018 12:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: CHRISTOPHER L.BRUNGA Company: BRUNGARDT OIL AND LEASING I Phone: (75) 848-4975

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls.
DV Tool set at 914' w/250 sx cement.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2018 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report: Perfs:

Had a deep hole in casing. Squeezed with 250 sx cement. Drilled out and casing still leaked. Ran tubing to 2900' and pumped 100 sx cement. Pulled tubing to 1400' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 720' and pumped 50 sx cement w/100 # hulls. Circulated cement, but lost circulation. POOH. Pumped 100 sx cement to fill casing. Visually checked cement and it was down 60' - 75'. Braden head full of cement.

GPS: 39.08653 -098.6968

INVOICED
JUL 12 2018

Remarks: QUALITY CEMENTING TICKET # 4830

Plugged through: TBG

District: 04 Signed Ray A. Dinkel (TECHNICIAN) CM

KCC WICHITA

MAY 17 2018

RECEIVED

MAY 03 2018