

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-19111-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 2-22S-12W
363 feet from S Section Line, 1658 feet from E Section Line
Lease Name: HELMERS B Well #: 3
County: STAFFORD Total Vertical Depth: 3627 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>8045</u>	<u>CIBP</u>		<u>3400</u>		<u>WITH 2 SX CMT</u>
Op Name: <u>C & B OPERATING INC.</u>	<u>PROD 4.5</u>		<u>3619</u>	<u>1078</u>	<u>WITH 100 SX CMT</u>
Address: <u>PO BOX 65</u> <u>ST JOHN, KS 67576</u>	<u>SURF 8.625</u>		<u>285</u>		<u>WITH 225 SX CMT</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2018 3:00 PM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: ROBIN AUSTIN Company: RAMA OPERATING Phone: (620) 549-3234

Proposed Plugging Method: SET CIBP @ 3400' WITH 2 SX CMT. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/25/2018 1:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

6/22/18: SET CIBP @ 3400' WITH 2 SX CMT ON TOP. 6/25/18: 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 45 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3434	3627		

INVOICED
JUL 16 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Ken Scofield
(TECHNICIAN)

RECEIVED
JUL - 2 2018
KCC DODGE CITY

12ms