

TB:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-01459-00-00  
Spot: NENESESW Sec/Twnshp/Rge: 6-24S-14E  
1057 feet from S Section Line, 2845 feet from E Section Line  
Lease Name: WINTERSCHIED Well #: 18  
County: WOODSON Total Vertical Depth: 1724 feet

Operator License No.: 34827  
Op Name: C3OIL, LLC  
Address: 600 ARROWHEAD DR  
NEW STRAWN, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	1693		15 SX
SURF	10	30		5 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2018 2:00 PM  
Plug Co. License No.: 33413 Plug Co. Name: TITUS WELL SERVICE LLC  
Proposal Rcvd. from: CHRIS HAAS Company: \_\_\_\_\_ Phone: (913) 515-5329

Proposed Plugging Method: Well perforated at 750' and 250'. Run 2" tubing 1724. Spot 25 sks oin bottom. Pull pipe to 750' Spot 25 sks cement. Pull tubing to 250' Pump cement to top. Fill well and outside of casing.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/19/2018 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1697', pumped 25 sxs cement, pulled tubing to 750', pumped 25 sxs cement, pulled tubing to 250' pumped 80 sxs cement to surface, casing shot @ 750' & 250', gel spacers between cement plugs,

Perfs:

Top	Bot	Thru	Comments
1693	1724		

RECEIVED  
KCC DIST # 3  
JUN 25 2018  
CHANUTE, KS

MT

INVOICED  
JUL 16 2018

Remarks:

Plugged through: TBG

District: 03

Signed Mitch Heffern  
(TECHNICIAN)

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



15-0788-01459

Cement or Acid Field Report  
 Ticket No. **3954**  
 Foreman Ricky Ledford  
 Camp Eureka, KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-19-18	1021	Winterschick #18	6	24	14	Woodson	Ks
Customer C-3 Oil			Unit #	Driver	Unit #	Driver	
Mailing Address 600 Arrowhead Dr. City New Stanton			102	Rex L.			
			112	Kenneth			
			121	Dave A.			
State	Zip Code	Safety Meeting AL K DB GM					
Ks	66839						

Job Type 2 1/2" oil well Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/8"  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. 14" - 14.8" Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 7" Cement Left in Casing \_\_\_\_\_ Water Gal/SK 7.0 Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety meeting - Rig up to 2 3/8" tubing. Plugging orders as follows:  
25 sacks @ 1100'  
gel-spacer  
25 sacks @ 750'  
gel-spacer  
80 sacks @ 250' to surface.  
 "Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	25	Mileage / 3 <sup>rd</sup> well of 2	3.95	98.75
C203	130 sacks	60/40 Permian Cement	12.75	1657.50
C206	450 <sup>#</sup>	Gel	.20	90.00
C205	50 <sup>#</sup>	2 3/8" core for bottom plug	.60	30.00
C206	300 <sup>#</sup>	gel-spacers	.20	60.00
C214	20 <sup>#</sup>	hulls	.45	9.00
C108A	5.59	tan mileage bulk truck	m/c	345.00
C113	3 hrs	80 Blt vac. work	85.00	255.00
C224	3300 gals	city water	10.00/1000	33.00
INVOICED				
JUL 10 2018				
			Subtotal	3328.25
			-5%	(166.41)
			Sales Tax	249.62
Authorization by <u>Cris Hies</u> Title <u>Owner</u>			Total	<b>3398.97</b>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.