

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-01339-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 34-8S-16W
2970 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DENNIS Well #: 1
County: ROOKS Total Vertical Depth: 3465 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3192		
SURF	8.625	228		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2018 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. DBA Phone: _____

Proposed Perforations: 3073' - 3132'
Plugging No top stage cement records.
Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2018 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 1600', 1220', 800' and 220'. Ran tubing to 2907'. Swift Services pumped 100 sx cement w/200 # hulls. Pulled tubing to 1750' and pumped 100 sx cement w/150 # hulls. Cement circulated. PTOH. Tied on to casing with a swage and pumped 65 sx cement. Cement circulate out of 8 5/8" surface casing.

GPS: 39.31535 -099.09123

Perfs:

Top	Bot	Thru	Comments
3124	3132		
3120	3131		
3110	3114		
3071	3073		

INVOICED

JUN 16 2018

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JUN 12 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAY 31 2018