

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20129-00-02
Spot: SWSWSENW Sec/Twnshp/Rge: 28-11S-22W
2887 feet from S Section Line, 3657 feet from E Section Line
Lease Name: KLINE Well #: 1
County: TREGO Total Vertical Depth: 4050 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4045		200 SX
SURF	8.625	208		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/03/2018 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: CHRIS SCHOENHOFER Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Perforations: 3556' - 3557', 3617' - 3674' and 3896' - 3912'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/03/2018 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 2200', 1750' and 625'. Ran tubing to 3528' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 3228' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2228' and pumped 150 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 200 psi.

GPS: 39.06744 -099.77257

Perfs:

Top	Bot	Thru	Comments
3896	3912		
3617	3774		
3556	3557		


INVOICED
JUL 16 2018

Remarks: QUALITY CEMENT TICKET # 815

Plugged through: TBG

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

CM

MAY 17 2018

Form CP-2/3

MAY 08 2018

RECEIVED