

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22446-00-01
Spot: SWNENWSW Sec/Twnshp/Rge: 16-34S-10W
1995 feet from S Section Line, 678 feet from W Section Line
Lease Name: BLUNK Well #: 1
County: BARBER Total Vertical Depth: 5300 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4612		WITH 2 SX CMT
PROD	5.5	5298	2800	WITH 200 SX CMT
SURF	8.625	314		WITH 215 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/09/2018 3:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4630' & 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/19/2018 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 4612' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 608' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 352' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Top	Bot	Thru	Comments
4680	4690		

INVOICED
JUL 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
JUN 25 2018
KCC DODGE CITY

km8