

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20892-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 1-3SS-12W
1140 feet from N Section Line, 1500 feet from W Section Line
Lease Name: ACHENBACH B Well #: 1
County: BARBER Total Vertical Depth: 4805 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4790	3000	WITH 150 SX CMT
SURF	10.75	303		WITH 300 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/25/2018 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Revd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND TO 4740' WITH 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350' WITH 100 SX CMT. PLUG AT 60' WITH 40 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 05/25/2018 10:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND BACK TO 4722' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 608' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 352' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4790	4805	OH	

INVOICED
JUL 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
MAY 25 2018
KCC DODGE CITY