

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21120-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 35-34S-12W
1563 feet from S Section Line, 1083 feet from E Section Line
Lease Name: NORMA Well #: 2
County: BARBER Total Vertical Depth: 4850 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4849	3000	WITH 150 SX CMT
SURF	8.625	377		WITH 300 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/05/2018 8:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS & 4 SX CMT. PLUG AT 600' WITH 12 SX GEL & 40 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2018 9:50 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4600' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 576' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 384' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4775	4779	CSG	

INVOICED

JUL 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE & CEMENTING.

Plugged through: TBG

District: 01

Signed Stephen J. Alper
(TECHNICIAN)

518

RECEIVED
JUN 13 2018
KCC DODGE CITY

Form CP-2/3