

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22272-00-00
Spot: NWSWSWSE Sec/Twnshp/Rge: 27-32S-10W
645 feet from S Section Line, 2410 feet from E Section Line
Lease Name: OHARA Well #: 1
County: BARBER Total Vertical Depth: 4470 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
PROD	5.5	4468	1800	WITH 125 SX CMT
SURF	8.625	311		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/28/2018 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: RYAN MOLZ Company: CHIEFTAN OIL Phone: (620) 886-1816

Proposed Plugging Method: SET CIBP @ 4320'. CUT & PULL CASING. RIH WITH TBG. PLUG AT 600' WITH 10 SX GEL FOLLOWED BY 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' TO SURFACE.

Plugging Proposal Received By: HEITH WALSH WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2018 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4300' WITH 2 SX CMT PLACED ON TOP. 1ST PLUG TIH TO 672'.
BREAK CIRCULATION WITH FRESH WATER THEN PUMP 10 SX GEL FOLLOWED
BY 50 SX CMT. 2ND PLUG AT 352' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX
CMT TO FILL HOLE. HOLE REMAINING FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4362	4404		CSG

INVOICED

JUL 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUL - 2 2018
KCC DODGE CITY

Form CP-2/3

KMS