

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-02810-00-00
Spot: NWNWSWSE Sec/Twnshp/Rge: 35-13S-17W
1039 feet from S Section Line, 2375 feet from E Section Line
Lease Name: BRAUN Well #: 1
County: ELLIS Total Vertical Depth: 3510 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3440		125 SX
SURF	8.625	213		255 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2018 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DENNIS Company: CITATION OIL & GAS CORP. DBA Phone: (785) 639-6310

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 600 # hulls and 22 50# sx gel.
PBTD - CIBP 3415' - 3436' - 3438'.
CIBP 3439' AR OH 3440' - 3510'.
LKC perforations: 3218' - 3224', 3237' - 3243', 3264' - 3280', 3284' - 3288' and 3324' - 3330'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2018 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

ELI Perforating perforated at 1700', 1100', 575' and 210'. Express Well Service ran in hole with tubing to 3383' and pumped 11 sx gel followed by 75 sx cement w/200 # hulls mixed in. Pulled tubing to 1650' and pumped 150 sx cement w/400 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 5 1/2' casing and pumped 40 sx cement w/300 psi. Shut in pressure 50 psi. Rigged to 8 5/8" surface casing and it was full of cement.

GPS: 38.87422 -099.17776

Perfs:


INVOICED
JUL 16 2018

Remarks: BASIC OILFIELD CEMENTING CO. TICKET # 16733

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

MAY 17 2018

RECEIVED

MAY 18 2018

Form CP-2/3