

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-059-23926-00-01  
Spot: NWNWNWNE Sec/Twnshp/Rge: 33-15S-20E  
5131 feet from S Section Line, 2493 feet from E Section Line  
Lease Name: SALISBURY Well #: 1  
County: FRANKLIN Total Vertical Depth: 791 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 65749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	778		65 SX
SURF	6.25	40		15 SX

Well Type: EOR UIC Docket No: E24111.57 Date/Time to Plug: 03/22/2018 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: REX R. ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RI W/ 1" TBG INSIDE THE PROD CSG TO 776', PMP CMT THRU TBG, CIRC SAME TO SURF, POOH 1" TBG, "TOP OFF" PROD CSG W/ CMT, PRESS UP ON SAME AND SHUT WELL-IN. WILL RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW" DEPTH, AND CLEAN UP LOC.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE  
Date/Time Plugging Completed: 03/22/2018 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down inside the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe. Hooked onto casing and pumped cement into well and pressured to 500 psi and shut in. A total of 25 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
726	736		

RECEIVED  
KCC DIST # 3  
JUN 20 2018  
CHANUTE, KS

RD

INVOICED

JUL 16 2018

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] E. G. R. S. I.  
(TECHNICIAN)