

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-21718-00-01  
Spot: SWNWSWSE Sec/Twnshp/Rge: 29-16S-11W  
978 feet from S Section Line, 2468 feet from E Section Line  
Lease Name: DOLECHEK A Well #: 3  
County: BARTON Total Vertical Depth: 3501 feet

Operator License No.: <u>3682</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>CONNELL, MARK ALLEN</u>	PROD	4.5	3395		100 SX
Address: <u>606 W ALBRO ST</u> <u>CLAFLIN, KS 67525</u>	SURF	8.625	339		185 SX

Well Type: SWD UIC Docket No: D20884.0 Date/Time to Plug: 05/16/2018 8:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: MARK CONNELL Company: CONNELL, MARK ALLEN DBA Phone: (620) 786-1228

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/16/2018 2:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report: Perfs:

Perforated at 1450', 750' and 300'. Ran tubing to 3200' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 2500' and pumped 60 sx cement. Pulled tubing to 1600' and pumped 60 sx cement. Pulled tubing to 700'. Circulated cement to surface with 50 sx cement. Pulled tubing. Tied on to casing and circulated cement to surface on backside with 60 sx cement.

GPS: 38.62602 -098.56201

INVOICED  
JUL 16 2018

Remarks: QUALITY OILWELL CEMENTING  
Plugged through: TBG

District: 04 Signed Bruce Rodie (TECHNICIAN) *cm*  
Received KANSAS CORPORATION COMMISSION  
MAY 22 2008 JUN 12 2018  
CONSERVATION DIVISION WICHITA, KS  
Form CP-2/3