

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-059-24183-00-00  
Spot: NENENENW Sec/Twnshp/Rge: 33-15S-20E  
4972 feet from S Section Line, 2696 feet from E Section Line  
Lease Name: PAULINE SCOTT Well #: 7 W1  
County: FRANKLIN Total Vertical Depth: 780 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	762		82 SX
SURF	6.25	40		15 SX

Well Type: EOR UIC Docket No: E24111.8 Date/Time to Plug: 06/13/2018 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: REX R. ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH 1" TBG TO 760', PMP IN & CIRC CMT TO SURF, POOH 1" TBG, "TOP OFF" PROD CSG, PRESS UP TO 3-400 PSI, SWI. WILL RETURN AT A LATER DATE TO CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: RYAN DULING Witness Type: NONE  
Date/Time Plugging Completed: 06/13/2018 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out of the casing and topped the well off with cement. Squeezed casing and shut well in at 200 psi. A total of 20 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
728	732		

RECEIVED  
KCC DIST # 3  
JUN 20 2018  
CHANUTE, KS

RD

INVOICED

JUL 16 2018

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] ECRS  
(TECHNICIAN)