

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20929-00-00
Spot: NENWNE Sec/Twnshp/Rge: 6-16S-10W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: ZVOLANEK Well #: 1
County: ELLSWORTH Total Vertical Depth: 3358 feet

Operator License No.: 3682
Op Name: CONNELL, MARK ALLEN
Address: 606 W ALBRO ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR	5.5	3273		
PROD	5.5	3352		125 SX
SURF	8.625	342		190 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2018 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: MARK CONNELL Company: MARK ALLEN CONNELL Phone: (620) 786-1228

Proposed Plugging Method: PER KCC RUELS & REGS. WELL HAS BACKER PACKER WITH TAIL PIPE STUCK BETWEEN 3250'-3275'

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/06/2018 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1350', 1050', AND 392'. RUN TUBING TO BOTTOM TAGGING AT 3273'. PULLED UP 2 JTS AND PUMPED 35 SX'S COMMON WITH 3% CC. PULLED TUBING UP TO 1350' AND PUMPED 35 SX'S COMMON WITH 3% CC. PULLED TUBING UP 700' AND WAITED 1.5 HOURS. RUN TUBING BACK DOWN AND TAGGED CEMENT AT 1134'. PULLED TUBING TO 1050' AND PUMPED 35 SX'S COMMON WITH 3% CC. PULLED TUBING TO 392' AND CIRCUALTED CEMENT TO SURFACE. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3352	3358	OH	

INVOICED
JUL 16 2018

Remarks: WELL WAS SQUEEZED WITH 250 SX'S CEMENT AT 450' TO 600' ON 7-1-2010. TA - N.O.V. WELL. QUALITY OIL WELL CEMENT TICKET #C-785.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK