

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22708-00-00
Spot: NESWNENW Sec/Twnshp/Rge: 10-19S-9W
780 feet from N Section Line, 1895 feet from W Section Line
Lease Name: SOEKEN Well #: 1
County: RICE Total Vertical Depth: 3360 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3266		
PROD	5.5	3350	1705	175 SX
SURF	8.625	316		200 SX
TI	2.875	3287		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2018 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC. Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/21/2018 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS & TUBING. SAND PERFS TO 2850' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 1705' AND PULL TO 1200' AND PUMPED 8 SX'S GEL FOLLOWED BY 35 SX'S COMMON 4% CC AND 100 LBS COTTON HULLS. PULL CASING ON UP TO 800' AND WAIT 1 HOUR. ATTEMPTED TO TAG CEMENT AT 1200', CEMENT WAS AT 1350'. RUN CASING BACK IN TO 1200' AND PUMPED 35 MORE SX'S COMMON CEMENT, PULLED CASING TO 800' AND PUMPED 35 SX'S COMMON WITH 3% CC, PULLED CASING TO 365' AND CIRCUALTED CEMENT TO SURFACE. PULLED CASING OUT AND TOPPED OFF. USED APPROX. 225 SX'S.

Perfs:

Top	Bot	Thru	Comments
3302	3305	CSG	
2915	2919	CSG	

INVOICED
JUL 16 2018

Remarks: QUAILTY OILWELL CEMENT #793
Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

[Handwritten mark]