

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-02268-00-00
Spot: SWNESWSE Sec/Twnshp/Rge: 1-34S-15E
929 feet from S Section Line, 1914 feet from E Section Line
Lease Name: BURROWS Well #: 6
County: MONTGOMERY Total Vertical Depth: 870 feet

Operator License No.: 7582
Op Name: DELOZIER, ORVAL & STEVENS, FLOY
Address: PO BOX 64
DEWEY, OK 74029

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	0		0 SX
SURF	10	90		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/22/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: JOHN ELMORE Company: _____ Phone: (620) 725-5744

Proposed Plugging Method: Per KCC regulations

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 06/20/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 820' gelled hole spotted 5 sack plug. Pulled 1" and perforated casing at 550' and 225'.
Ran 1" back into 550' and spotted 10 sack plug. Pulled up to 225' and circulated cement to surface with 103 sacks cement. Pulled 1" and topped well off. A total of 118 sacks of cement with 3% gell was used to plug this well. Well was cut off and location restored.

RECEIVED
KCC DIST # 3
JUN 26 2018
CHANUTE, KS

DS

INVOICED
JUL 16 2018

Remarks: OPERATOR CLEANING UP SOME OF HIS TA'D WELLS.
Plugged through: TBG

District: 03

Signed Duane A Sims
(TECHNICIAN)