

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22918-00-00
Spot: SWSENWNW Sec/Twnshp/Rge: 26-12S-25W
1250 feet from N Section Line, 735 feet from W Section Line
Lease Name: HLADEK Well #: 1-26
County: TREGO Total Vertical Depth: 4550 feet

Operator License No.: 35036 String Size Depth (ft) Pulled (ft) Comments
Op Name: DRIPPING OIL, LLC PROD 5.5 4548 175 sx
Address: PO BOX 1380 SURF 8.625 266 175 sx
DRIPPING SPGS, TX 78620

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/09/2018 9:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: JOHN FOSE Company: DRIPPING OIL, LLC Phone: (785) 324-2658

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 13 sx gel and 400 # hulls.
Perforations: 4009' - 4015'.
Port Collar at 2258' w/1950 sx cement. Did not circulate.
Ran 1" liner down to top of cement and filled the backside.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2018 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report: Perfs:

Ran 1" tubing down the backside and pumped 45 sx cement. Good circulation of cement. Tied to casing and pumped 50 sx cement w/200 # hulls, followed by 13 sx gel, followed by 220 sx cement. Shut in pressure 900 psi.

John Fose plugged this well for the equipment.

GPS: 38.98352 -100.07222

INVOICED
JUL 16 2018

Remarks: GLOBAL CEMENTING TICKET # 3032

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

MAY 31 2018

RECEIVED

MAY 11 2018