

4-060888

5-7

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-23,888.0000
150'S. & 50'E. of
N2 NW /4 SEC. 24, 20 S, 12 W
4470 feet from S section line
3910 feet from E section line

Operator license# 6170

Lease: Spece Well # 2

Operator: Globe Operating, Inc.

County: Barton

Address: P.O. Box 12
Great Bend, Kansas 67530

Well total depth 3425 111.31 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 299 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 11:00 A.M. Day: 7 Month: May Year: 1996

Plugging proposal received from: Mike Kelso/Manny

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 210 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 03 1996

Plugging Proposal Received by: Herb Deines CONSERVATION DIVISION
Plugging operations attended by agent? All[], Part[], None[X] WICHITA, KS


Completed: Hour: 2:15 P.M., Day: 7, Month: May, Year: 1996

Actual plugging report: 8 5/8" to 299' w/265 sxs. 5 1/2" to 3425' w/150 sxs. Perfs at 3142' - 3145'. Sanded to 3100' and spotted 5 sxs cement with dump bailer. Shot casing loose at 2223' and pulled to 1400'. Mixed and pumped 100 sxs cement with 300# hulls. Pulled casing to 600' and pumped 40 sxs cement with 200# hulls. Pulled casing to 250' and circulated cement to surface with 30 sxs. Pulled casing and topped with 20 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1807 GL

I did did not observe the plugging.

DATE 6-10-96
INV. NO. 45759


(agent)
Form CP-2/3