

4-060887

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

5-9

API Number: 15-009-23,129.0000

E2 NW NW /4 SEC. 24, 20 S, 12 W
4620 feet from S section line
4290 feet from E section line

Operator license# 6170

Lease: Spece Well # 1

Operator: Globe Operating, Inc.

County: Barton

Address: P.O. Box 12
Great Bend, Kansas 67530

Well total depth 3426 111.34 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 9:00 A.M. Day: 9 Month: May Year: 1996

Plugging proposal received from: Mike Kelso/Manny

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 210 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 03 1996
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 2:30 P.M., Day: 9, Month: May, Year: 1996

Actual plugging report: 8 5/8" to 250' w/200 sxs. 5 1/2" to 3424' w/150 sxs. Perfs at 3254' - 3255'. Sanded to 3200' and spotted 5 sxs cement with dump bailer. Shot casing loose at 2530' and pulled to 1400'. Mixed and pumped 100 sxs cement with 300# hulls. Pulled casing to 600' and pumped 40 sxs cement with 200# hulls. Pulled casing to 250' and circulated cement to surface with 30 sxs. Pulled casing and topped with 25 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: 1797 GL

I did [] / did not [X] observe the plugging.

[Signature]
DHX (agent)
Form CP-2/3

INVOICED
DATE 6-10-96
INV. NO. 45758