

4-060590

10-6 15.009.15600.0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 3-8-39

E2 NE NE /4 SEC. 24 , 20 S, 12 W  
4620 feet from S section line  
330 feet from E section line

Operator license# 5229

Lease York-Marchand well # 1

Operator: Phillips Petroleum

County Barton

Address: R.R. #3 - Box 20A  
Great Bend, Kansas 67530

Well total depth 3365 feet <sup>109.36</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 13 Inch @ 215 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Mike's Testing and Salvage, Inc. License# 31529

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 3:00P.M. Day: 6 Month: October Year: 94

Plugging proposal received from: Mike Kelso - Matt Johnson (Phillips Pet)

Company: Mike's Testing and Salvage, Inc. Phone: 316-938-2943

Were: Order 300 sxs. 60/40 posmix - 10% gel with hulls.  
5 1/2" liner to 820' with packer.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 6:30P.M., Day: 6, Month: October, Year: 94

Actual plugging report: 13" to 215' w/240 sxs. 7" to 3307'. 5 1/2" liner to 820' with packer. Sand with 3 sxs. cement - plug with dump bailer every 70' from T.D. to 2950' w/7 sxs. cement on top of sand with dump bailer. Pulled all of 5 1/2" liner with packer. Shot 7" loose at 1600'. Pulled casing to 1300'. Laid down two joints due to holes in the casing. Mixed and pumped 150 sxs. cement with 300# hulls. Pulled casing to 570' and pumped 30 sxs. cement with 200# hull with cement to surface. Pulled casing and topped with 30 sxs. cement.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD     BAD X Anhy.plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation: 1795 GL

I did X did not     observe the plugging.

[Signature]  
DH (agent)  
Form CP-2/3

**INVOICED**  
DATE 11-3-94  
BILL NO. 41571