

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-12055-00-00
Spot: N2 NW NE Sec/Twnshp/Rge: 22-20S-12W
4950 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: STECKEL B Well Number: 1
County: BARTON Total Vertical Depth: 3399 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 0
Production: Size 7 feet: 3386
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/03/2002 9:15 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 500 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/03/2002 5:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

10 3/4" S.P. at unknown depth.
7" casing at 3386'.
Ran perforating tool to 1450' (deepest penetration) and perfed casing.
Ran tubing to 1450' and spotted 390 sxs to circulate.
Pulled tubing to 720' and circulated with 80 sxs cement and 500# hulls.
Pulled all tubing and squeezed 7" casing with 30 sxs cement to Max. P.S.I. 200#. S.I.P. 200#.
Annulus took no cement. Max. P.S.I. 200#.
Total of 500 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED

JUN 27 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. BRACKEEN TANK - WATER.

Plugged through: TBG

District: 04

Signed _____

Roger S. Moses
(TECHNICIAN)

22-20-12W / 53

ALPINE OIL & ROY #1 STECKEL B APP N2 NW NE

Contr. QUAKER DRLG BARTON County

E. 1837 RE Comm. Comp. 7-24-53 IP 539 BOPD
PHY POT

Tops	Depth	Datum
HEEB	3013	-1176
LANS	3148	-1311
ARB	3384	-1547
TD	3399	-1562

Casing

7" 3386

ACID 500: SWB 10 BOPH

BUCKBEE SW POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS