

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE-NE-SW, Sec. 22, T 20 S, R 12 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 0-09-20,615

_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 4461

Lease Name CHURCHILL Well # 2

Operator: MARNER OIL COMPANY
Name & Address: 415 WEST 5th
ELLENWOOD, KANS.
67526

County BARTON
Well Total Depth 2445 feet \$111.96
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 244

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor WELSO CASING PULLING License Number 6050

Address BOX 176 CHASE, KANS. 67524

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

VERBAL PLUGGING ORDERS GIVEN TO BUCK UNRUH

(company name) WELSO CASING PULLING (phone) 316-938-2457

were: 8 5/8" - 244 FT SR. CUC #1225 5th CMT. -> 5 1/2" SET @ 2444 FT #100 CMT.

TOP OF CASE'S 2412-22, AT BOTTOM 5 5th CMT. - SAND TO 2350 FT

AND #1 5 5th CMT. SHOT CSG (1) RECOVERED 2750 FT 5 1/2" CSG.

ORDERED 165 5th 50/50 Pozmix 4% GEL-3% CA-CL. - 15 5th GEL - 5 5th HULL'S.

AND 8 5/8" PLUG. PUMP IN 8 5/8" SURFACE PIPE WITH PUMP TRUCK.

Signed Mary Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 PM Day: 11th Month: OCT. Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 165 5th 50/50 Pozmix 4% GEL-3% CA-CL. - 15 5th GEL -

5 5th HULL'S AND 8 5/8" PLUG. - PUMPED IN 8 5/8" S.P.

PUMPED IN: - 4 5th HULL'S - 25 5th CMT. - 10 5th GEL - 1/2 5th HULL'S -

40 5th CMT. - 5 5th GEL - 1/2 5th HULL'S. - RELEASE PLUG.

AND 100 5th CMT. - MAX. PRESSURE 750 PSI SHUT. IN @ 200 ^{PSI}

Remarks: (CEMENTED BY SUN CMT.)

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED RECEIVED STATE CORPORATION COMMISSION

DATE 10-27-83 OCT 14 1983

INV. NO. 5933-W CONSERVATION DIVISION Wichita, Kansas

Signed Mary Schmidt
(TECHNICIAN)