

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009-22206.0000

NE-NW-SE, Sec. 22, T. 20 S, R. 12 W

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5347

Lease Name A-J<sup>+</sup> RUBY WILSON Well # (1)

Operator: OONDOR ENERGY  
Name & Address: 606 HIRSOH  
ELLENWOOD, MO. 67526

County BARTON

Well Total Depth 2450 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 261 FT

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor SUN OIL WELL CEMENTING License Number \_\_\_\_\_

Address BOX 169 - GREAT BEND, MO. 67530

Company to plug at: Hour: 10:00 AM Day: 31<sup>st</sup> Month: JAN Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO RECON PULLY

(company name) ROCKHOLD ENGINEERING, INC. (phone) 316-792-2506 sk

were: 8 5/8" - 261<sup>ft</sup> SP. CMT. - 175<sup>ft</sup> CMT. -> 4 1/2 SET @ 3449<sup>ft</sup> / 100<sup>ft</sup> CMT

FEEDS TOP. 3404<sup>ft</sup> 10 - SHOT 4 1/2" CSG TWICE - RECOVERED 2600<sup>ft</sup>.

AT BOTTOM 4<sup>th</sup> CMT. 50<sup>th</sup> SAND AND 4<sup>th</sup> CMT.

ORDER 165<sup>th</sup> 5/8<sup>th</sup> FEMIX - 4% GEL - 3% CA-CL -> 17<sup>th</sup> GEL.

4<sup>th</sup> HULL'S. AND 8 5/8" FLUG - PUMP IN WITH PUMP TRUCK.

Signed Mason Schmidt  
(TECHNICIAN) (D.O.C.)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 AM Day: 31<sup>st</sup> Month: JAN Year: 1983

ACTUAL PLUGGING REPORT PUMPED IN WITH PUMP TRUCK

PUMPED IN 4 1/2" CSG -> 4<sup>th</sup> HULL'S -> 12<sup>th</sup> GEL -> 25<sup>th</sup> CMT.

5<sup>th</sup> GEL, REL PLUG. AND 140<sup>th</sup> CMT.

MAX. PRESSURE 475<sup>PSI</sup> CEMENTED BY SUN CMT.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

MAR 1 1983

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

VOICED  
MAR 24 1983

Signed Mason Schmidt  
(TECHNICIAN) (D.O.C.)

30606-W