

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE-SE-SW, Sec. 22, T 20 S, R 12 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-20,612

990 feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

2310 feet from W/E section line

Operator License # 7461

Lease Name CHURCHILL Well # 1

Operator: MARKER OIL COMPANY
Name & Address 415 WEST 5TH
ELLINWOOD, KANS.
67526

County BARTON

Well Total Depth 2467 feet \$111.68

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 241

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor WELSO CASING PULLING License Number 6050

Address BOX 176 CHASE, KANS. 67524

Company to plug at: Hour: 9:00 AM Day: 11 Month: Oct. Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO BUCK ANDRUH.

(company name) WELSO CASING PULLING (phone) 316-938-2457

were: 8 5/8" - 241 FT SR. CUL. w/ 250 CMT. -> 5 1/2" SET @ 2452 FT w/ 100 CMT.

PLUG BACK T.D. 3420 FT - TOP OF PERFS 2397 FT

PLUG BOTTOM UNIT WITH 5 CMT. - SAND TO 2350 AND w/ 5 CMT.

ORDERED 165 50/50 FORMIX 4% GEL-3% CA-CL, 15 GEL, 5 HULL'S

8 5/8" PLUG. PUMP IN 8 5/8" SURFACE WITH PUMP TRUCK.

SHOT OSC(2) RECOVERED 2700 FT. Signed [Signature] (TECHNICIAN) 801C

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:15 AM Day: 11 Month: Oct Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 165 50/50 FORMIX 4% GEL-3% CA-CL-15 GEL,

5 HULL'S. AND 8 5/8" PLUG. PUMPED IN 8 5/8" WITH PUMP TRUCK.

PUMPED IN 4 HULL'S - 25 CMT - 10 GEL - 1/2 HULL'S -

40 CMT. -> 5 GEL - 1/2 HULL'S - RELEASE PLUG. AND

100 CMT. MAX. 700 PSF SHUT. IN 250 PSF

Remarks: (CEMENTED BY SAND CMT.)

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed [Signature] (TECHNICIAN) 801C

DATE 10-27-82

OCT 14 1983

INV. NO. 5932-W

CONSERVATION DIVISION Wichita, Kansas