

6-050139

7-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-04929.0000

NE NE NE /4 SEC. 22, 20 S, 12 W
4950 feet from S section line
330 feet from E section line

Operator license# 31298 Lease Steckle B well # 3

Operator: S & S Oil County Barton

Address: 1128 North 14th Street Well total depth 3361 feet
Ponca City, Oklahoma 74601 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 215 feet

109.23

Aband. oil well XX, Gas well , Input well , SWD , D & A

Plugging contractor: Chase Well Service License# 6123

Address: P. O. Box 355, Great Bend, Kansas

Company to plug at: Hour: PM Day: 13 Month: July Year: 1994

Plugging proposal received from: Jerry Sorrel

Company: S & S Oil phone: 405-765-8010

Were: Packer stuck in 4 1/2" casing at 640'. 22 jnts of 2 3/8" tubing above packer, and 25 jnts of 2 3/8" tubing below packer. Holes in the 4 1/2" casing and in 8 5/8" tubing. 3/4" rods run in tubing with a scrapper on it stuck at 250'. Rods pulled back out. Decision to cement down 2 3/8" tubing. Agreement that if the well circulated before 24 bbls of slurry was pumped, the well would be flushed and other options would be considered. Ordered out 50 sx common, 200 sx 60/40 poz, 10% gel.

Plugging Proposal Received by: Jerry Sorrel
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 4:45 PM, Day: 13, Month: July, Year: 1994

Actual plugging report: Cellar dug out, braiden head exposed, pulled slips and pulled 15' of bad 4 1/2" casing. Ran 5 joints 2 3/8" tubing and screwed back on to 2 3/8" tubing looking up. Pumped 50 sx 60/40 poz, 10% gel, followed by 50 sx common. Cement circ out of 8 5/8" annulus. Backed off 2 3/8" tubing at 150'. Pumped 40 sx 60/40 poz, 10% gel down 4 1/2" casing. Cement circ out of 8 5/8" annulus. Packed off braiden head. Pumped 85 sx 60/40 poz, 10% gel. Developed 250# pressure maximum. No shut in. Cement coming back up braiden head. Annular space filled.

Remarks: Allied cementing on location.
Condition of casing(in hole): GOOD BADXXXX Anhy. plug: YESXXX NO
Bottom plug(in place): YESXXX, CALC XXX, NO Dakota plug: YESXXX, NO
Plugged through TUBING XX, CASING Elevation: 1815 GL

I did did not observe the plugging.

INVOICED

DATE 7-27-94

INV. NO. 40896

7-13

SEP 28 1994

RECEIVED
STATE CORPORATION COM
JUL 18 1994
CONSERVATION DIVISION
Wichita, Kansas
Bruce D. Basye
(agent)