

2-18-88

6 061434

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-22,661.0000

NW, SEC. 17, T 20 S, R 12 (W)K

2970 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6842

Operator: Dixie Oil Inc.

Name & Address: Box 23

Great Bend, Ks. 67530

Lease Name Welsh Farms Well # 1

County Barton 113.75

Well Total Depth 3500 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well  Gas Well  Input Well  SWD Well  U&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Box 698 Great Bend, Ks. 67530

Company to plug at: Hour: 9:00 AM Day: 18 Month: Feb Year: 19 88

Plugging proposal received from D. B. Pullie

(company name) Rockhold Engineering Inc. (phone) 316-793-3060

were: Order 125 sks 65/35 Pozmix 10% Gel 2% Econlite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30 PM Day: 18 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 320' w/200 sks. 5 1/2" set at 3349' w/75 sks.

Top perf at 3321'. Plugged bottom w/sand and 5 sks cement to 3260'. Shot pipe two times and recovered 2684'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 100 sks cement w/800 Psi.

RECEIVED STATE CORPORATION COMMISSION

MAR 2 1988 3-2-88

Remarks: By B. J. Titan

(if additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Gilbert G. Scheck (TECHNICIAN)

Gilbert G. Scheck

INVOICED

DATE 3-2-88

INV. NO. 19955