

6 062483

8-21 364  
API NUMBER 15- 009-20,223.0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE, SEC. 17, T 20 S, R 12 W/E  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30601  
Operator: Northstar Investment, Inc.  
Name & Address: 8433 Huntington  
Wichita, Kansas 67202

Lease Name Schartz Well # 1  
County Barton 112.06  
Well Total Depth 3448 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 249'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address Box 768, Great Bend, Kansas 67530

Company to plug at: Hour: 9:00A.M. Day: 21 Month: August Year: 19 91

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: Order 200 sks. of 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:15P.M. Day: 21 Month: August Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" set at 249' w/300 sks. 5 1/2" set at 3438' w/100 sks.

Top perf. at 3189'. Plugged bottom with sand and 5 sks. cement to 3125'.

Shot pipe 3 times and recovered 1625'. Pumped in 5 1/2" casing and circulated cement to surface. Pulled all casing and hooked on to 8 5/8" and squeezed to 300 P.S.I.

Used 200 sks. cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 05 1991

Remarks: By: B.J. Services Ran Line to 3000'.  
(If additional description is necessary, use BACK of this form.)

I (did not observe) observe this plugging.

INVOICED  
DATE 9-13-91  
INV. NO. 33114

Signed [Signature] (TECHNICIAN)