

6-050102

2-1

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-15619.0000

SW NE NW /4 SEC. 26, 20 S, 12 W
4290 feet from S section line
4290 feet from E section line

Operator license# 5568

Lease Marchand well # 3

Operator: Midway Drilling, Inc.

County Barton

Address: P. O. Box 1325
Great Bend, Kansas 67530

Well total depth 3479 feet 113.06
Conductor Pipe: inch @ feet
Surface pipe 10 Inch @ 260 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: P. O. Box 1325, Chase, Kansas 67524

Company to plug at: Hour: PM Day: 1 Month: February Year: 1993

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pulling phone: 316-938-2943

Were: 5 1/2" set at 3356' with 150 sx. PBTD 3285'. Perfs at 3252' to 3272'. Sand to 3200', bail dump 5 sx cement. Shoot casing below 1500', pull to 1500', pump cement down 5 1/2" casing, pull casing. Repeat until the hole is full.

Plugging Proposal Received by: Bruce Basye
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 5:17 PM, Day: 1, Month: February, Year: 1993

Actual plugging report: Plugged bottom off as indicated above. Casing parted at approx. 1288'. Pumped 130 sx 65/35 poz, 8% gel, casing on vacuum on backside and on 5 1/2". Shut in backside, pumped 35 sx 65/35 poz, 8% gel. Pulled 700' casing to 588'. Pumped 165 sx 65/35 poz, 8% gel. Pulled 300' casing. Pumped 30 sx 65/35 poz, 8% gel. Ordered 200 sx 65/35 poz, 8% gel. Ran wireline, lt cem at 40', hvy cem at 320' in casing. Pulled 1 jnt casing. Pumped 35 sx 65/35 poz 8% gel, cem circ. Pulled 280' casing, topped off w/ 10 sx 65/35 poz 8% gel.

Remarks: Elevation ground level-1812'. Base Hutchinson Salt member-1390' Anhydrite-700'. Allied cement on location. Plugged checked on 2 Feb 93 fell 5 feet in hole.

I did[XX] / did not[] observe the plugging.

INVOICED

DATE 2-17-93

INV. NO. 37367

Bruce D. Basye
(agent)
Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
FEB 24 1993

2-493