

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04958-00-00

Spot: CNWNWSE

Sec/Twnshp/Rge: 28-20S-12W

2310 feet from S Section Line, 2310 feet from E Section Line

Lease/Unit Name: BROWN

Well Number: 1

County: BARTON

Total Vertical Depth: 3460 feet

Operator License No.: 5141

Op Name: ZENITH DRILLING CORPORATION

Address: PO BOX 780428
WICHITA, KS 67278

Conductor Pipe: Size

feet:

8 1/2.45

Surface Casing: Size 8.625

feet: 278

250 SX CMT

Production: Size 5.5

feet: 3453

125 SX CMT

Liner: Size

feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/26/2002 1:00 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed
Plugging
Method:

Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 09/26/2002 4:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3380' and topped with 5 sxs cement using a dump bailer.

Parted casing at 310'.

TIH with tubing and stacked out at 640'.

Tied onto and circulated cement with 220 sxs cement and 500# hulls.

POOH. Hole full of cement.


RECEIVED
KANSAS CORP COM
2002 OCT -4 P 1:28

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 10-7-02

INV. NO. 2003060610

SEP 27 2002

28-20-12, NW NW SE 53

BARTON County

E 1856 RB Comm. 8-21-58 Comp. 10-10-58 IP 80 BOPD

Tops	Depth	Datum
ANH	630	1226
HEEB	3050	-1194
BR LM	3176	-1320
LANS	3194	-1338
B/KC	3408	-1552
CONG	3426	-1570
ARB	3438	-1582
TD	3460	-1604

Casing	
8"	278
5"	3453

DC: ACID 500: SWB 6 BOPH

CHASE-SILICA POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

7-10
 7-11
 7-12
 7-13
 7-14
 7-15
 7-16