

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-12238-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 28-20S-12W  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: SPACIL Well Number: 8  
County: BARTON Total Vertical Depth: 3451 feet

Operator License No.: 5141  
Op Name: ZENITH DRILLING CORPORATION  
Address: PO BOX 780428  
WICHITA, KS 67278

Conductor Pipe: Size \_\_\_\_\_ feet: \$12.16  
Surface Casing: Size 8.625 feet: 280 250 SX CMT  
Production: Size 5.5 feet: 3442 125 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2002 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/25/2002 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3380' and topped with 5 sxs cement using a dump bailer.  
Shot casing free at 2230'.  
Pulled up to 1475' - mixed and pumped 105 sxs cement with 300# hulls.  
Pulled up to 675' - spotted 40 sxs cement with 100# hulls.  
Pulled up to 250' - circulated cement with 65 sxs cement and 100# hulls.  
POOH. Hole full of cement.

RECEIVED  
KANSAS CORP COMM  
2002 OCT -4 P 1:28

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 10-7-02

WV. NO. 2003060610

SEP 27 2002

1940:20

ALPINE OIL & ROYALTY #8 SPACIL 28-20-12W 53  
 NW SW NE  
 Contr. QUAKER DRLG BARTON County  
 E 185<sup>1</sup>/<sub>4</sub> RB Comm. Comp. 1-9-59 IP 25 BOPD

Tops	Depth	Datum
ANH	635	1219
HEEB	3042	-1188
BR LM	3165	-1311
LANS	3182	-1328
B/KC	3401	-1547
ARB	3428	-1574
TD	3451	-1597

Casing  
 8" 280  
 5" 3442  
 CO: DD 3451: 1500' 01H/10 HR:  
 SWB 1 BOPH/4 HR: ACID 500:  
 SWB 1 1/2 BOPH/5 HR

CHASE-SILICA POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS