

4- 060363

11-17

92  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-24,486-0000

SE NW NE /4 SEC. 28, 20 S, 12 W  
4290 feet from S section line  
1650 feet from E section line

Operator license# 3309 Lease Spacil well # 1

Operator: Eagle Petroleum, Inc. County Barton

Address: P.O. Box 106 Well total depth 3491 feet <sup>113.46</sup>  
Bushton, Kansas 67427 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 264 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 10:00A.M Day: 17 Month: November Year: 92

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 250 sxs. 60/40 posmix - 8% gel. and hulls.

Plug through casing.

Ran flow rate test. Good injection rate to perfs.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 5:30P.M., Day: 17, Month: November, Year: 92

Actual plugging report: 8 5/8" to 264'. 5 1/2" to 3490' w/125 sxs.

Injection rate test good. Pump 100 sxs. cement w/100# hulls and

displaced to 2000'. Shot at 1900' - 1800' - 1700' - 1600'. Recovered

1600' of casing, mix and displace 20 sxs. of gel to 800'. Pull casing

to 800' and pump 75 sxs. cement. Pull 400' of casing. Pump 80 sxs.

cement with cement to surface. Pulled casing and topped with 10 sx.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Allied Cementing.

NOV 23 1992

Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING X. Elevation: 1849 GL     

Wichita, Kansas

**INVOICED**

I did [X] / did not [    ] observe the plugging.

*[Signature]*  
E.A.S.

DATE 12-1-92

(agent)

INV. NO. 36940

Form CP-2/3