

8-31

6 061591

API NUMBER 15-009.07393.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Operator: Lasmo Energy Corp
Name & Address Box 1365
Great Bend, Ks. 67530

NE, SEC. 28, T 20 S, R 12 W/E
2970 feet from S section line
2310 feet from E section line

Lease Name Spacil Well # 7

County Barton 112-19

Well Total Depth 3452 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 1:00 PM Day: 31 Month: August Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) _____

were: 350 sks 60/40 Pozmix 6% Gel 3% Cal Cl 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1988

CONSERVATION DIVISION
Wichita Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00PM Day: 31 Month: August Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 280' w/250 sks. 5 1/2" set at 3443' w/150 sks.

Top perf at 3424'. Plugged bottom w/sand and 5 sks cement to 3375'.

Pipe parted at 480'. Pumped in 2" tubing and circulated cement from 800'

to surface. Pulled tubing and 480' of casing. Pumped in 8 5/8" and squeezed

w/350 sks cement w/500 Psi.

Remarks: R. I. Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

Signed Gilbert G. Scheck
(TECHNICIAN)

D

DATE 9-20-88

Gilbert G. Scheck

INV. NO. 22302