

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19038-00-02
Spot: NENENE Sec/Twnshp/Rge: 28-20S-12W
4950 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: SPACIL Well Number: 1
County: BARTON Total Vertical Depth: 3560 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

Conductor Pipe: Size feet: 8/15.70
Surface Casing: Size 8.625 feet: 260 225 SX CMT
Production: Size 5.5 feet: 3560 250 SX CMT
Liner: Size feet:

Well Type: SWD UIC Docket No: D20129.0 Date/Time to Plug: 10/01/2002 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 938-2943

Proposed Plugging Method: Ordered 555 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perf at 1475' and 350'.
Cemented production string and tubing in hole.
3" tubing at 3483' in the hole.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/01/2002 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

09-30-2002 - Allied Cementing pumped 50 sxs at 3000' to cement bottom perms - unwitnessed.
10-01-2002 - Mike's Testing & Salvage shot production string at 2425' and 1485' - could not pull string.
Opened up 8 5/8" and tied onto 3" - pumped 415 sxs 60/40 pozmix to circulate cement into pit. Shut in 8 5/8".
Shot perf at 350' and opened up 5 1/2".
Pumped 55 sxs to circulate cement to surface.
Shut in 5 1/2" - pumped 3" to pressure with 5 sxs cement.
Max. P.S.I. 225#. S.I.P. 200#.

RECEIVED
KANSAS CORP COM
2002 OCT -11 P 1:26

Remarks: ALLIED CEMENTING COMPANY-TICKET #13054.

Plugged through: TBG

District: 04

Signed [Signature]

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 10-7-02

NO. 2003060610

OCT 02 2002

GOUGH DAVIS & QUAKER

#1

SPACIL

53

28-20-12W
NE NE NE

Contr. QUAKER

BARTON

County

E 1842RB

Comm.

Comp.

10-7-49

IP

D & A

Tops	Depth	Datum
Auth	620	+1222
HEEB	3028	-1186
BR LM	3153	-1311
LANG	3171	-1329
CONG	3423	-1521
ARB	3482	-1640
T.D.	3490	-1648

Casing
8" 260 N.S.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS