

4-060379

3-11 15.009.00303.0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 7-56

NW SW SE /4 SEC. 16, 20 S, 12 W  
990 feet from S section line  
2310 feet from E section line

Operator license# 5238

Lease Hulme G-I well # 45  
*Originally #1*

Operator: Petroleum, Inc.

County Barton

Address: 301 N. Main  
Wichita, Kansas 67202

Well total depth 3465 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 244 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Co Tools License#     

Address:     

Company to plug at: Hour: 10:00A.M Day: 11 Month: March Year: 93

Plugging proposal received from: Terry Naylor

Company: Petroleum, Inc. Phone: 316-793-8471

Were: Ordered 75 sxs. common and 375 sxs. 60/40 posmix - 8% gel.  
Perf base of salt at 1400' and anhydrite at 640'.  
Fluid level 500'.  
Tubing and rods pulled prior to plugging.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 11:15A.M, Day: 11, Month: March, Year: 93

Actual plugging report: 8 5/8" to 244'. 5 1/2" to 3400'. Tied onto casing and pumped 75 sxs. common followed by 60/40 posmix - 8% gel. with good circulation out of annulus. Shut in annulus valve and pumped 300 sxs. 60/40 posmix - 8% gel. and 200# hulls. Max. 500#. S.I.P. 100#. Opened annulus valve and pumped 50 sxs. cement with 50# hulls. Annulus cemented from 640' perfs. to surface. Final S.I.P. 200#. Free fluids circulated out removed from well site.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 15 1993

3-15-93

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation: 1831 GL

I did[ X ] / did not[      ] observe the plugging.

*Herb Deines*  
E.R.C.

(agent)

Form CP-2/3

INVOICED  
DATE 3-18-93  
INV. NO. 37487